BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of Work: Patching pot holes in main and cross roads of Balaji layout, Bhadrappa layout, Maruthinagara, BB Nagara, Shanthinikethana and Surroundings areas in ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Issued to Sanjayreddy H.J	
				In Figures	In Words
1	108.84	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification NO. 406, Page No. 157 / Item No. 20.18 / PWD SR 2016-17	Cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
2	616.73	KSRRB 3000: Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2, No. 250 / Item No. 35.5 PWD SR 2016-17	Sqm	328.60	Rupees Three Hundred Twenty Eight and Sixty Paise Only

Signature of the Contractor

11/07

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

11/07